BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT48591

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2021-22, Date: 01.10.2021

Name of Work:Maintenance of water supply Existing borewells at Bellahalli, Thirumenahalli and Chokkannahalli Village Surrounding area in Ward No. 05, Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
1	2800	A) Rewinding Labour Charges of lifting of non functioning submersible Pump set along with cable and GI Pipes	Each	114.42	Rupees One Hundred Fourteen and Forty Two Paise Only
2	45	Transportation of pumping machineries	Each	944.73	Rupees Nine Hundred Forty Four and Seventy Three Paise Only
3	7	Rewinding of Submersible Pump Sets (BWSSB SR 14-15 P-58 I-A) 10 HP	No.	5022.81	Rupees Five Thousand Twenty Two and Eighty One Paise Only
4	8	(BWSSB SR 14-15 P-58 I-A) 7.5 HP	No.	4011.95	Rupees Four Thousand Eleven and Ninety Five Paise Only
5	15	(BWSSB SR 14-15 P-58 I-A) 12.5 HP	No.	6177.48	Rupees Six Thousand One Hundred Seventy Seven and Forty Eight Paise Only
6	15	(BWSSB SR 14-15 P-58 I-A) 15.0 HP	No.	6088.26	Rupees Six Thousand Eighty Eight and Twenty Six Paise Only
7	140	B) Replacement of Motor Parts: Pump Bowls (BWSSB SR 14-15 P-58 I-B)	No.	323.31	Rupees Three Hundred Twenty Three and Thirty One Paise Only
8	45	Intermediate Piece (I.P) With IP Leaded Bronxe bush (BWSSB SR 14-15 P-58 I-B2)	No.	750.54	Rupees Seven Hundred Fifty and Fifty Four Paise Only
9	45	Upper Flange (BWSSB SR 14-15 P-59 I-C3)	No.	346.4	Rupees Three Hundred Forty Six and Forty Paise Only
10	45	Lower Housing (BWSSB SR 14-15 P-59 I-C4)	No.	565.79	Rupees Five Hundred Sixty Five and Seventy Nine Paise Only
11	90	Guide vane (BWSSB SR 14-15 P-58 I-B5)	No.	202.07	Rupees Two Hundred Two and Seven Paise Only
12	45	Impeller Shell moulded with aluminium Bronze) (BWSSB SR 14-15 P-58 I-B6)	No.	277.12	Rupees Two Hundred Seventy Seven and Twelve Paise Only
13	45	Discharge outlet (D.O) Bearing D.O Steel Bush P. (BWSSB SR 14-15 P-58 I-B7)	No.	548.47	Rupees Five Hundred Forty Eight and Forty Seven Paise Only
14	30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) (BWSSB SR 14-15 P-58 I-B10)	No.	692.8	Rupees Six Hundred Ninety Two and Eighty Paise Only
15	45	Pump Couping (Stainless Steel) (BWSSB SR 14-15 P-58 I-B12)	No.	357.95	Rupees Three Hundred Fifty Seven and Ninety Five Paise Only
16	60	Stud and Nuts (BWSSB SR 14-15 P-59 I-C8)	Each	92.37	Rupees Ninety Two and Thirty Seven Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Word
17	30	Motor Base With Pin (BWSSB SR 14-15 P-59 I-C11)	Each	427.23	Rupees Four Hundred Twenty Seven and Twenty Three Paise Only
18	30	Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No.	5300.99	Rupees Five Thousand Three Hundred and Ninety Nine Paise Only
19	30	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No.	4933.59	Rupees Four Thousand Nine Hundred Thirty Three and Fifty Nine Paise Only
20	35	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No.	498.61	Rupees Four Hundred Ninety Eight and Sixty One Paise Only
21	45	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No.	1207.16	Rupees One Thousand Two Hundred Seven and Sixteen Paise Only
22	45	Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No.	131.21	Rupees One Hundred Thirty One and Twenty One Paise Only
23	45	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No.	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
24	45	D.O Bearing P. No. 44 / I No. 10.2.7 PRED SR (2012-13)	No.	299.16	Rupees Two Hundred Ninety Nine and Sixteen Paise Only
25	210	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No.	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
26	20	Allen Screw P. No.44 / I No. 10.2.9 RDPR SR (2012-13)	No.	26.24	Rupees Twenty Six and Twenty Four Paise Only
27	45	Pump Key (Stainless Steel) P. No. 45 / I No. 10.2.11 RDED SR (2012-13)	No.	131.21	Rupees One Hundred Thirty One and Twenty One Paise Only
28	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No.	1417.1	Rupees One Thousand Four Hundred Seventeen and Ten Paise Only
29	45	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No.	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
30	45	Strainer P. No. 45 / I No. 10.2.15 RDED SR (2012-13)	No.	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
31	45	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No.	262.43	Rupees Two Hundred Sixty Two and Forty Three Paise Only
32	45	Labour Chargesw (Over Hauling Only) P. No. 45 / I No. 10.2.18 PRED SR (2012-13)	No.	583.63	Rupees Five Hundred Eighty Three and Sixty Three Paise Only
33	45	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	997.22	Rupees Nine Hundred Ninety Seven and Twenty Two Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
34	50	Lock Ring P. No. 45 / I No. 10.3.11 PREC SR (2012-13)	Each	89.22	Rupees Eighty Nine and Twenty Two Paise Only
35	45	a) Carbon Housing P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	498.61	Rupees Four Hundred Ninety Eight and Sixty One Paise Only
36	45	Top Carbon/Ferrodo padding P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
37	45	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush P. No. 46 / I No. 10.3.16 APRDED SR (2012-13)	Each	419.88	Rupees Four Hundred Nineteen and Eighty Eight Paise Only
38	45	Circillps P. No. 45 / I No. 10.3.17 PREC SR (2012-13)	Each	52.49	Rupees Fifty Two and Forty Nine Paise Only
39	90	Genaral Itmes Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11 63 Amps	No.	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
40	440	Threading of GI Pipes 50mm Dia P. No. 15 / I No.3.11.6 PRED SR (2012-13)	No.	26.24	Rupees Twenty Six and Twenty Four Paise Only
41	2500	Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19	Mtr	151.16	Rupees One Hundred Fifty One and Sixteen Paise Only
42	45	Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19)	No	944.73	Rupees Nine Hundred Forty Four and Seventy Three Paise Only
43	300	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	178.4	Rupees One Hundred Seventy Eight and Forty Paise Only
44	300	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr	59.47	Rupees Fifty Nine and Forty Seven Paise Only
45	271.69	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	332.69	Rupees Three Hundred Thirty Two and Sixty Nine Paise Only
46	805	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 96, I.NO - 13.73.2, PWD SR 18-19)	Mtr	413.92	Rupees Four Hundred Thirteen and Ninety Two Paise Only
47	271.69	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	134.63	Rupees One Hundred Thirty Four and Sixty Three Paise Only
48	10	Supplying & delivery of brand 50mm Gate Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 15	No	1889.46	Rupees One Thousand Eight Hundred Eighty Nine and Forty Six Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Executive Engineer
Byarayanapura Division
BBMP, Bangalore-92

8/03

Signature of Contractor

Executive Engineer